



**US-75**

**41st Street**

**46th Street**

**49th Street**

**51st Street**

**I-44**

**I-44**

**US-75**

**Phase 5**

(36.098895, -96.007143)

**Widen US-75 to 6 lanes from 41st Street to 51st Street**

**Construct US-75 bridge over 51st Street while joining 51st Street under US-75**

**Replace existing US-75 bridges and ramps over 46th Street and 49th Street and reconstruct 46th Street and 49th Street under US-75**

**Complete several directional ramps and bridges at I-44/US-75 interchange**

**Phase 2**

(36.086433, -96.006755)

**Construct several directional ramps and bridges at I-44/US-75 interchange**

**Reconstruct US-75 from south of Mooser Creek to near 71st Street**

**Reconstruct US-75/61st Street Interchange, including 61st Street bridge over US-75**

**Reconstruct Skelly Drive from Union Avenue east to US-75**

**Phase 3**

(36.077194, -96.00543)

**Widen I-44 to 6 lanes east of the US-75 and widen the bridge over the Arkansas River**

**Construct I-44 bridge over Tulsa-Sapulpa Union Railway**

**Continue widening US-75 to 6 lanes south of the bridge over Mooser Creek**

**Construct Skelly Drive east of US-75**

**Complete US-75 Frontage Road and I-44 access road**